

4-071084

2-8

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-24,428-00-00

NE NW SE /4 SEC. 34, 12 S, 18 W
2310 feet from S section line
1650 feet from E section line

Operator license# 6484 Lease Jensen well # 1

Operator: Anderson Energy, Inc. County Ellis 119.50

Address: 200 East 1st. Street - #414 Well total depth 3677 feet
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet
Tom Larson Surface pipe 8 5/8 Inch @ 255 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# _____

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 8 Month: February Year: 94

Plugging proposal received from: Tom Larson

Company: Consultant Anderson Energy, Inc. Phone: 316-265-7929

Were: 8 5/8" - 255' S.P. cwc. w/160 sxs. cement. 5 1/2" casing set @
3674' w/165 sxs. cement. Elv. 2087' - Anhy. 1352' - casing good.
Squeeze at 755' with 172 sxs. cement circulated. Proposal 250 sxs.
65/35 pozmix - 10% gel and 5 sxs. hulls. Pump in with pump truck.
1) Perforate 3 holes 120° at 1352' and 2050'. Pump in 5 1/2" casing
with 25 sxs. cement followed with 13 sxs. bentonite gel. Squeeze
with 150 sxs. cement also squeeze annulus with 50 sxs. cement if necessary.

Plugging Proposal Received by: Marion J. Schmidt - Dennis L. Hamel
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 11:00A.M., Day: 8, Month: February, Year: 94

Actual plugging report: Anderson Energy ordered 250 sxs. cement. 13 sxs.
bentonite gel and 5 sxs. hulls. Pumped in 5 1/2" casing with pump truck.
1) Perforated 5 1/2" casing at 1352' and 2050'.
2) Pumped in 5 1/2" casing with 25 sxs. cement then with 13 sxs. gel then
150 sxs. cement with 2 sxs. hulls mixed in cement. Max. pressure
750 P.S.I. Shut in @ 550 P.S.I.
3) 5 1/2" x 8 5/8" annulus full of cement. Cement visable in head.

Remarks: Cemented by Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did not observe the plugging. Marion J. Schmidt

INVOICED
DATE 2-21-94
INV. NO. 39975

Marion J. Schmidt
(agent)

*Rec'd
02-24-1994
2-21-94
MJC*