

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 051-23823-00-00

SW, Sec. 34, T 12 S, R 18 W

2310 feet from ~~S~~ section line

1155 feet from ~~W~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5804

Lease Name Morintzer Well # 1

Operator: Drilling LTD
Name & 410 17th St
Address Suite 1140
Denver Colo.

County E. 11is

Well Total Depth 3750 feet 121.88

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 7/8 feet 217

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor C. & R. Drilg. License Number 5813

Address Denver Colo. 410 17th St.

Company to plug at: Hour: 3:30 PM Day: 14 Month: 3 Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Jim Mortinger

(company name) C. & R. Drilg. ⁹¹³(phone) 628-3699

were: order 220 sx. cement 50/50 pozzolix 6% gel

15x hulls. 1. 8 7/8 plug 15x Flow Seal

Heavy mud between all plugs.

Pump cement down drill pipe

Elev- 2126 Anhydrite 1390-1432 Arbuckle 3700

Dakota 1800
326

Signed Walef Battchayor
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None

Operations Completed: Hour: 4:25 PM Day: 14 Month: 3 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 3700 for 45 mi.

25 SX @ 3700

25 SX @ 1400

100 SX @ 650 mixed with 15x Flow Seal.

40 SX @ 225 15x hulls pushed plug to 40'

10 SX @ 40

Remarks: 10 SX in Rat Hole

Cementing w. Halliburton

RECEIVED
CORPORATION COMMISSION
MAR 26 1984
03-26-1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 3-29-84

INV. NO. 09-2
3-14

Signed Walef Battchayor
(TECHNICIAN)