

6-090486

5-12

214
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-24,794-0000

NW NE SE /4 SEC. 18, 12 S, 19 W
2310 feet from S section line
990 feet from E section line

Operator license# 03655 Lease Oscar Hagen Well # 1

Operator: Staab Energy & Leasing County Ellis

Address: 2514 Haney Drive Well total depth 3848 feet
Hays, Kansas 67601 Conductor Pipe: inch @ feet
(913)628-1326 Surface pipe 8 5/8 Inch @ 221 feet

125.06

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Shields Drilling Company, Inc. License# 05655

Address: Russell, Kansas

Company to plug at: Hour: PM Day: 07 Month: May Year: 1992

Plugging proposal received from: Burton Beery

Company: Shields Drlg. Company, Inc. phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 1620 feet with 20 sacks Rat hole: 15 sacks

2nd plug @ 880 feet " 100 " Mousehole: 10 sacks

3rd plug @ 270 feet " 40 "

4th plug @ 40 feet " wiper plug & 10 sks.

5th plug @ feet "

Plugging Proposal Received by: Ed Schumacher P.I.R.T. III

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 9:00 PM, Day: 12, Month: May, Year: 1992

Actual plugging report: Hole reported plugged as above.

Order 195 sx 60/40 pozmix w/ 6% gel and 1 sx celloflake or flowcel.

Remarks: Elevation: 2232 GL, Anhydrite depth: 1594 - 1638 feet
Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: NO
Plugged through drill pipe: YES
Did Not penetrate Arbuckle, cemented by Allied Cementing Company

I did[], did not[X] observe the plugging.

INVOICED

DATE 6-5-92

INV. NO. 35423

5-12 JUL 0 8 1992

Ed Schumacher
Ed Schumacher
(agent)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
For Wichita, Kansas
1992
06-01-1992