

1-30

To: 6 031329  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 051-21,440A-00-01  
NE NE NE 21 12 19  
SEC. , T S, R W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 8572

Operator: Reach Oil Corp  
Name & Address: 229 E. Williams #500  
Wichita, Ks. 67202

4950 feet from S section line

330 feet from E section line  
Wann Howard

Lease Name OWWO Well # 1

County Ellis 124.80

Well Total Depth 3840 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 228

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Plains Inc. License Number 4072

Address Ness City, Ks.

Company to plug at: Hour: PM Day: 30 Month: Jan Year: 19 90

Plugging proposal received from Clint Base

(company name) Plains Inc. (phone)

were: 8 5/8" set at 228 w/165 sks. 4 1/2" set at 3614' w/200 PBTD 3584'.

Perf 3504 - 06. Shots at 1530 and 800. Holes at 1200' Wireline to bottom.

Order 350 sks 65/35 poz 10% gel 500# hulls. B. J. Titan Cement Co.

Werth Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: PM Day: 30 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 1900' cwc. Lay down tubing. Squeeze

4 1/2" w/300 sks cement blend w/500# hulls mixed into max psi 200#. Close in psi 200#.

Squeeze 8 5/8" w/50 sks cement blend to max psi 300#. Close in psi 300#.

Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED and observed this plugging.

DATE 2-26-90

INV. NO. 27573

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow