

4-020070

11-23

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-23,233-0000
20' W. of
NE SE NW /4 SEC. 10, 12 S, 20 W
3630 feet from S section line
2990 feet from E section line

Operator license# 30680

Lease: Fries Well # 1

Operator: Geist Oil Operations

County: Ellis 128.21

Address: 807 Grant
Victoria, Kansas 67671
785-735-2664

Well total depth 3945 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 258 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: L&M Well Service License# 31172

Address: 24 S. Lincoln, Russell, Kansas 67665

Company to plug at: Hour: 2:00 P.M. Day: 23 Month: November Year: 1998

Plugging proposal received from: Bill Geist

Company: Geist Oil Operations Phone: 785-735-2664

Were: Ordered out 175 sxs 60/40 pozmix - 10% gel - 13 sxs gel - 500# hulls.
Prod. Perfs at 3915' - 3920'; 3841' - 3845'; 3833' - 3837'; 3724' - 3730';
3689' - 3693'; 3519' - 3522'; 3424' - 3430'.
Casing squeezed at 3709' - 3717' and 1508' - 1583'.
In 1997 casing squeezed at 985' - 867' with 120 sxs.
Well reported to have hole in casing - fluid level at 600'.

11-25-1998

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 6:30 P.M., Day: 23, Month: November, Year: 1998

Actual plugging report: 8 5/8" set at 258'. 4 1/2" set at 3900' w/200 sxs cement.
Ran tubing to 3720' and spotted 40 sxs cement with 300# hulls.
Pulled tubing to 3000' and pumped 13 sxs gel spacer.
Pulled tubing to 1600' and pumped 25 sxs cement.
Tubing POOH - tied onto 4 1/2" and staged 86 sxs cement with 200# hulls.
Max. P.S.I. 800#. S.I.P. 400#.
Annulus pressured to Max. P.S.I. 500#. S.I.P. 500#.

Remarks:

Condition of casing(in hole): GOOD BAD X
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING X, CASING. Anhy. plug: YES X NO
Dakota plug: YES X, NO
Elevation: 2203 GL

I did [X] did not [] observe the plugging.

Jay F. [Signature]
(agent)

~~11-23-1998~~
DEC 01 1998
60396