

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

SEP 6 1967
09-06-1967
CONSERVATION DIVISION
Wichita, Kan.

15-051-20114-00-00
J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Lattimer of Raymond Oil Co. Inc. has this
date requested permission to plug the following described well:

Mr. Lattimer guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Inc.,

Complete Address: 410 4th Nat'l Bank Bldg. Wichita, Kansas

Lease Name: Jensen Well No. 1

Location: NW NE SE Sec. 34 Twp. 12 Rge. 18 (E)(W) X

County Ellis Total Depth 3097 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lattimer was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 745' and displace
100 sc cement thru drill pipe. Heavy mud to 210' set cementing plug
and displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Leo J. Mearns
Conservation Division Agent