



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

AUG 25 1972
08-25-1972
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-051-20846-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Draper of Dreiling Drlg. has this
date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Inc.

Complete Address: Victoria, Kansas

Lease Name: Robber Well No. 1

Location: NE NW SW Sec. 10 Twp. 12 Rge. (E)(W) 19

County: Ellis Total Depth 3900' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Draper was instructed to plug the well as follows:

Run pits, circulate heavy mud, set cementing plug at 660' and displace
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. F. Massey
Conservation Division Agent