

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-051-20132-00-00

RECEIVED  
OIL & GAS CONSERVATION COMMISSION  
ACT 9 1967  
10-09-1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Miller of Dreiling & Sons has this

date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling & Sons, Inc/

Complete Address: Victoria, Kansas

Lease Name: Hall Well No. 1

Location: SE NW NW Sec. 10 Twp. 12 Rge. 20 (E)(W) X

County Ellis Total Depth 3605 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Miller was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace  
100 sc cement thru drill pipe. Heavy mud to 150' set cementing plug  
and displace 25 sc cement thru drill pipe. Heavy mud to 40' set cem  
enting plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat  
hole with 2 sc cement.

Very truly yours,

Ray J. Massey  
Conservation Division Agent