

15-051-21011-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Ellis County, Sec. 21 Twp. 12S Rge. 19 (W)

Location as "NE/CNW/SW" or footage from lines C NW NE NE  
Lease Owner S & K Oil Company  
Lease Name WANN Well No. #1  
Office Address P. O. Box 559, Tulsa, Oklahoma 74101  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 17 1975  
Application for plugging filed (verbally) February 17 1975  
Application for plugging approved (verbally) February 17 1975  
Plugging commenced February 17 1975  
Plugging completed February 17 1975  
Reason for abandonment of well or producing formation No commercial quantity of gas or oil encountered.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3856 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	207'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st Plug Set @ 775' with 70 sacks cement  
2nd Plug Set @ 185' with 20 sacks cement  
3rd Plug Set @ 40' with 10 sacks cement  
Plug was down @ 7:00 a.m., February 17, 1975

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 19 1975  
02-19-1975  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Abercrombie Drilling, Inc.  
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Jerry A. Langrehr, V.P. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr  
801 Union Center, Wichita, Kansas 67202  
(Address)



Subscribed and sworn to before me this 18th day of February, 1975  
Nancy E. Haner  
Notary Public.

CONTRACTOR'S WELL LOG

15-051-21011-00 -00

OPERATOR:	S & K Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	WANN #1
LOCATION:	C NW NE NE Section 21-12S-19W Ellis County, Kansas
GEOLOGIST:	Frank Bennett
SPUD DATE:	February 4, 1975
COMPLETION DATE:	February 17, 1975

0	35	Clay
35	60	Rock
60	200	Sand
200	685	Shale
685	760	Sand
760	960	Shale
960	1180	Sand
1180	1502	Shale
1502	1544	Anhydrite
1544	2120	Shale
2120	3242	Lime & Shale
3242	3307	Lime
3307	3419	Lime & Shale
3419	3445	Lime
3445	3538	Lime & Shale
3538	3559	Lime
3559	3810	Lime & Shale
3810	3856	Lime
	3856	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 19 1975  
02-19-1975  
CONSERVATION DIVISION  
Wichita, Kansas

Drilled 207' of 12 1/4" surface hole. Ran 294.16' of 8-5/8" 32# surface pipe, Set @207' K.B. Cemented with 150 Sacks Quickset Cement. Cement circulated. Plug was down @7:30 p.m., February 4, 1975.

Plugged & Abandoned: 1st Plug Set @ 775' with 70 sacks cement, 2nd Plug Set @ 185' with 20 sacks cement, 3rd Plug Set @ 40' with 10 sacks cement. Plug was down @7:00 a.m., February 17, 1975. State Plugger: Mr. Leo Massey.

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the WANN #1, C NW NE NE Section 21-12S-19W, Ellis County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr  
Jerry A. Langrehr

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 18th day of February, 1975.

Nancy E. Haner  
Nancy E. Haner, Notary Public

