

15-051-21440-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ellis County. Sec. 21 Twp. 12S Rge. 19 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
NE NE NE

Lease Owner Zenith Drilling Corp.  
Lease Name Wann Well No. 1  
Office Address 200 W. Douglas, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed Jan. 21 1978  
Application for plugging filed (verbally) Jan. 21 1978  
Application for plugging approved (verbally) Jan. 21 1978  
Plugging commenced Jan. 21 1978  
Plugging completed Jan. 21 1978  
Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3840  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Set 1st plug at 600' with 70 sacks  
2nd plug at 185' with 20 sacks  
3rd plug at 40' with 10 sacks  
Plug was down at 5:30 a.m., January 21, 1978




(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Ass't. Secretary-Treasurer (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) *Jack L. Partridge*  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 19 78



*Sandra Richman*  
Sandra Richman Notary Public.

OPERATOR: Zenith Drilling Corp.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Wann #1  
 LOCATION: NE NE NE Section 21-12S-19W  
 Ellis County, Kansas  
 SPUD DATE: January 13, 1978  
 COMPLETION DATE: January 21, 1978

0	230	Surface soil, sand & shale
230	1490	Sand & shale
1490	1533	Anhydrite
1533	1925	Shale
1925	2302	Shale & sand
2302	2442	Shale
2442	2850	Lime & shale
2850	3021	Shale
3021	3342	Lime & shale
3342	3413	Shale
3413	3478	Lime & shale
3478	3515	Shale
3515	3555	Lime & shale
3555	3587	Lime
3587	3685	Lime & shale
3685	3775	Shale
3775	3840	Lime
	3840	Rotary Total Depth

Spud hole at 1:30 a.m., January 13, 1978. Drilled 230' of 12" hole. Ran 5 joints of 8-5/8" surface casing. Set at 228.39'. Cemented with 165 sacks common cement, 2% gel, 3% CaCl. Cement did circulate. Plug was down at 6:45 a.m., January 13, 1978.

T.D. 3840'. Set 1st plug at 600' with 70 sacks, 2nd plug at 185' with 20 sacks, 3rd plug at 40' with 10 sacks. Plug was down at 5:30 a.m., January 21, 1978. State Plugger - Leo Massey.

SAMPLE TOPS:

Anhydrite 1490  
 B/Anhydrite 1533

RECEIVED  
 STATE CORPORATION COMMISSION  
 02-07-1978  
 FEB 07 1978

STATE OF KANSAS )  
 )  
 COUNTY OF SEDGWICK )

CONSERVATION DIVISION  
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the Wann #1, NE NE NE Section 21-12S-19W, Ellis County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge, Ass't. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid on this 3rd day of February, 1978.



Sandra Richman  
 Sandra Richman, Notary Public