

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-051-23,679-00-00

LEASE NAME Bunker

WELL NUMBER 1

SPOT LOCATION E/2 NE SW

SEC. 10 TWP. 12 SRGE. 20 (E) (W)

COUNTY Ellis

DATE WELL COMPLETED 11-14-83

PLUGGING COMMENCED 11-14-83

PLUGGING COMPLETED 11-14-83

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR DaMar Resources, Inc.

ADDRESS P. O. Box 70, Hays, KS 67601

PHONE #(913) 625-0020 OPERATORS LICENSE NO. 9067

CHARACTER OF WELL  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? District #6

Is ACO-1 FILED? \_\_\_\_\_ IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION \_\_\_\_\_ DEPTH TO TOP \_\_\_\_\_ BOTTOM \_\_\_\_\_ T.D. 3916'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	259'	-0-

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Mudladen fluid @ 3916' - 3905'  
20 sks cement @ 3905'  
20 sks cement @ 1620' 10 sks cement @ rathole  
100 sks cement @ 870'  
40 sks cement @ 300'  
10 sks cement @ 40'

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Emphasis Oil Operations LICENSE No. 750  
ADDRESS P. O. Box 506, Russell, KS 67665-0506

STATE OF KANSAS COUNTY OF RUSSELL, SS.

Joe K. Branum (EMPLOYEE OF OPERATOR) OR  
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT  
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND  
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND  
CORRECT, SO HELP ME GOD.

(SIGNATURE) Joe K. Branum

(ADDRESS) P. O. Box 506, Russell, KS 67665

SUBSCRIBED AND SWORN TO BEFORE ME THIS 16 DAY OF November, 1983



Glenda R. Tiffin  
Glenda R. Tiffin, NOTARY PUBLIC

MY COMMISSION EXPIRES: February 6, 1984.

RECEIVED STATE CORPORATION COMMISSION FORM CP-4 REVISED 06-83

NOV 17 1983  
11-17-1983  
CONSERVATION DIVISION  
Wichita, Kansas

15-051-23679-00-00

EMPHASIS OIL OPERATIONS

P. O. Box 506

Russell, Kansas 67665-0506

DRILLERS LOG

OPERATOR: DaMar Resources, Inc.  
P. O. Box 70  
Hays, Kansas 67601

CONTRACTOR: Emphasis Oil Operations  
P. O. Box 506  
Russell, Kansas 67665-0506

LEASE: Bunker WELL: #1

LOCATION: E/2 NE SW  
Section 10-12S-20W  
Ellis County, Kansas

Total Rotary Depth: 3916'

Elevation:

Total Log Depth: No Log

Date Completed: 11-14-83

Commenced: 11-7-83

Status: Dry Hole

Casing: 8-5/8" @ 259' with 160 sks cement

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	40'	Anhydrite	1653'
Clay, Sand & Shale	262'	Shale	2940'
Shale	1080'	Shale & Lime	3631'
Sand	1310'	Lime	3888'
Redbed	1328'	Lime & Shale	3901'
Redbed & Shale	1611'	Lime (R.T.D.)	3916'

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

*Joe K. Branum*  
\_\_\_\_\_  
Joe K. Branum

Subscribed and sworn to before me this 16th day of November, 1983.

My Commission Expires: February 6, 1984.



RECEIVED  
STATE CORPORATION COMMISSION

*Glenda R. Tiffin*  
\_\_\_\_\_  
Notary Public

NOV 17 1983  
11-17-1983  
CONSERVATION DIVISION  
Wichita, Kansas