


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 16 Twp. 12 Rge. 19 (E) W (W)
Location as "NE/CNW&SW&" or footage from lines NW NW NW
Lease Owner Crescent Oil & Gas Corporation
Lease Name Gorrell Well No. 1
Office Address P. O. Box 485, Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 26 19 63
Application for plugging filed August 26 19 63
Application for plugging approved August 26 19 63
Plugging commenced August 26 19 63
Plugging completed August 26 19 63
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3830 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|---------|------------|
| | | | | | 8 5/8"- | -0- |
| | | | | | 250' | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set @ 600' w/20 sx cement
Plug set @ 240' w/20 sx cement
Plug set @ 40' w/20 sx cement

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1963
08-30-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address Box 173, Russell, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Carl E. Stacey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl E. Stacey
P. O. Box 485, Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27 day of August, 19 63

My commission expires January 11, 1965
Marilyn Spacil Notary Public.



INVOICED
DATE 8/30/63
INV. NO. 7674-W

15-051-04658-00-00

DRILLERS LOG

Gorrell No. 1

CASING RECORD: 8 5/8" @ 252.12 w/150 sx cement
 COMPANY: Crescent Oil & Gas Corp.
 CONTRACTOR: Red Tiger Drilling Co.
 COMMENCED: August 19, 1963
 COMPLETED: August 26, 1963

DESCRIPTION: NW NW NW
 16-12S-10W
 Ellis Co.,
 Kansas

ELEVATION: 2235 DF
 2238 RB

TOTAL DEPTH: 3830'

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u> |
|---------------------|-------------|-----------|----------------|
| Clay & Rock | 0 | 50 | |
| Rock | 50 | 70 | |
| Shale & Shells | 70 | 570 | |
| Sand & Shale | 570 | 820 | |
| Shale & Shells | 820 | 1070 | |
| Dakota Sand | 1070 | 1268 | |
| Red Bed | 1268 | 1572 | |
| Anhydrite | 1572 | 1611 | |
| Shale & Shells | 1611 | 1985 | |
| Shale Lime & Shells | 1985 | 2000 | |
| Shale & Shells | 2000 | 2460 | |
| Lime | 2460 | 2595 | |
| Shale & Lime | 2595 | 3258 | |
| Chalky Lime | 3258 | 3370 | |
| Lime | 3370 | 3491 | |
| Shale | 3491 | 3494 | |
| Lime | 3494 | 3755 | |
| Lime & Shale | 3755 | 3830 | |

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 30 1963
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle
 George A. Angle

Subscribed and sworn to before me this 29th day of August, 1963.

Dorinda V. Head
 Notary Public

My Commission Expires:
11-17-68