

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-091-19256-00-00

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1963
08-19-1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Don Pratt Oil Operations
Complete Address: Box 656 Hays, Kansas
Lease Name Armbrister Well No. 1
Location NW NE SE Sec. 10 Twp. 12 Rge. (E) (W) 20
County Ellis Total Depth 4010
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Knight Casing Pulling Co
Address: Chase, Kansas License No. 436
Operation Completed: Hour 3PM Day 14 Month 8 Year 63

The Above well was plugged as follows:

8 5/8" 170' circulated with cement - 4 1/2" 4009' with 150 sax cement- perf at 3631'

Set plug, sand back to 3600', set 4 sax cement with dump bailer, pulled 3250' 4 1/2" to 550', circulated hole with heavy gel mud, displaced 20 sax cement through 4 1/2" at 550', heavy mud to 200', displaced 20 sax cement through 4 1/2" at 200', heavy mud to 35', cement 35' to bottom cellar.

Mudding and cementing by Knight Company Pump Truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 8/20/63
INV. NO. 7604-w