

*W*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-051-00559-00-00

JUL 6 1964  
07-06-1964  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Morganstern & Specter  
Complete Address: Box 661 Russell, Kansas  
Lease Name Hamburg Well No. 1  
Location NW NE NW Sec. 9 Twp. 12 Rge. (E) (W) 20  
County Ellis Total Depth 4010  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kansas License No. 436

Operation Completed: Hour 5PM Day 2 Month 7 Year 64

The Above well was plugged as follows:

8 5/8 244' circulated with cement - 5 1/2" 4009' with 100 sax cement & squeezed with cement in Dakota section.

Sand back to 3990', set 4 sax cement with dump bailer, pulled 500' 5 1/2" started pipe and pumped hole full heavy mud through 5 1/2" at 500' displaced 20 sax cement through 5 1/2" at 500' - hole pressured up to 300# - heavy mud to 180', displaced 20 sax cement through 5 1/2" at 180' heavy mud to 35', cement 35' to bottom cellar.

Mudding and cementing by Knight Casing Pulling Co. pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edwin J. [Signature]*  
Well Plugging Supervisor

DATE 7/6/64  
INV. NO. 9406-W