

14

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

05-16-1969
RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1969
CONSERVATION DIVISION
Wichita, Kansas

15-051-20436-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Richard W. Norton & Robert M. Bergstein

Complete Address: Box 1666 Shreveport, La.

Lease Name Karlin Well No. 2

Location SE SE NW Sec. 8 Twp. 12 Rge. (E) (W) 20

County Ellis Total Depth 4050

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: _____

Plugging Contractor: Hellar Drlg.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 11:30A Day 14 Month 5 Year 1969

The Above well was plugged as follows:

RTD 4050' 8 5/8 csg set at 250' cwc. Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk cmt.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Murray
Well Plugging Supervisor

INVOICED

DATE 5/16/69

INV. NO. 9778-4