

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1969
CONSERVATION DIVISION
Wichita, Kansas

15051-20348-00-00

Operator's Full Name Home - Stake Production Company

Complete Address: 1015 Philtower, Tulsa, Oklahoma 74103

Lease Name Mai Well No. 1

Location SW NW SW Sec. 18 Twp. 12 Rge. (E) (W) 20

County Ellis Total Depth 4049'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486 Ellirwood, Kansas License No. 462

Operation Completed: Hour 11A Day 14 Month 5 Year 1969

The Above well was plugged as follows:

Total Depth 4049' 8 5/8 csg set at 247' cwc 140 sk.

5 1/2 csg set at 4040' cw 100 sk smt.

5 1/2 csg PBDT 3974 Perf. (3933-3937)

Filled 5 1/2 csg W/sd (3920-3974) Dumped 5 sk cmt W/dump bailer. (3880-3920)

Shutoff and recovered 2800' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel W/5 sk hulls, 130 sk 50-50 poz cmt 6% gel, 5 sk gel, plug and 10 sk cmt.

Cmt. (0-40) gel(40-240) Cmt. (240-800) Gel (800-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Rev. F. Massing
Well Plugging Supervisor

DATE 5/16/69

INV. NO. 9781-W