

15-051-22988-00-00

KANSAS

FORM CP-3  
Rev. 1-8-82

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,988 ✓200 Colorado Derby Building  
Wichita, KS 67202Operator's Full Name N-B CompanyComplete Address P. O. Box 506, Russell, Kansas 67665Lease Name ReitmayerWell No. #3Location SE SE NWSec. 17 Twp. 12 Rge. 20 (East) (West)County EllisTotal Depth 4050'Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒Other well as hereinafter indicated ☐Plugging Contractor Emphasis Oil OperationsAddress P. O. Box 506, Russell, Kansas 67665License No.         Operation Completed: Hour: 7:30AM Day: 30th Month: April Year: 19 82Plugging Operations attended by Agent?: All ☐ Part ☐ None ☒

The above well was plugged as follows:

8 5/8"-240' s.p. cuc. w/160 sacks common-2% Gel.-3% Cal. Cl.Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.Spot with drill stem with heavy mud between all plugs.1st plug @ 910' w/70 sacks of cement2nd plug @ 250' w/40 sacks cement3rd plug-solid bridge of hulls and plug at 40' w/10 sacks cementCirculate 10 sacks of cement in rat hole.Amount of Surface Casing: 240' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]

Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I was plugging a well on location of 15-14-14 Russell County at  
this wells plugging time.

RECEIVED

STATE CORPORATION COMMISSION

MAY 05 1982

INVOICED

E 5-14-82 CONSERVATION DIVISION  
Wichita, KansasSigned: [Signature]

Conservation Division Agent

NO. 169-W