

15-163-03290-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2-25-64
FEB 25 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name I. O. Miller
Complete Address: 619 Brown Bldg Wichita, Kans
Lease Name Croffoot Well No. 3
Location SW SE NE Sec. 11 Twp. 10 Rge. (E) (W) 20
County Rooks Total Depth 3844
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Apex Casing Pulling
Address: Hoisington, Kans License No. 544
Operation Completed: Hour 3PM Day 24 Month 2 Year 64

The Above well was plugged as follows:

8 5/8" 231' circulated with cement - 5 1/2" 3812' with 125 sax cement
Filled with sand to 3800', set 4 sax cement with dump bailer - pulled
2400' 5 1/2" to 500' - pumped 25 sax gel at 500' - hole pressured up - pulled
5 1/2" to 420' - spotted 20 sax cement at 420' - heavy mud to 200', displaced
20 sax cement through 5 1/2" at 200', heavy mud to 35', set bridge and
cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edon Letty*
Well Plugging Supervisor

INVOICED
DATE 2/27/64
INV. NO. 8677-w