

f

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

SEP 13 1977
09-06-77

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,727 - 0000 (of this well)

Operator's Full Name I. O. Miller, Inc. & Associates

Complete Address Box 124, Ellis, Kansas

Lease Name Croffoot C-G Well No. 11

Location App C NE SW Sec. 11 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3829'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor C & G Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 10 A Day 5 Month 9 Year 1977

The above well was plugged as follows:

RTD 3829' 8 5/8 csg set 212' cwc 150 sk. Flg. Mat 50550 poz 6& total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey
Well Plugging Supervisor

DATE 9-7-77
INV. NO. 5785W