

15-163-03525-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 5 1973  
CONSERVATION DIVISION  
Wichita, Kansas  
11-05-73

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water, Wichita, Kansas 67202

Lease Name C.A. Desbien Well No. 1

Location SE SE NW Sec. 12 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3744'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 10: A    Day 1 Month 11 Year 1973

The above well was plugged as follows:

Total depth 3744' 10 3/4 csg set at 358' cwc 200 sk.

7" csg set at 3740' cw 200 sk cem.

7" csg PBTB 3687' with top perf. (3584')

~~7" csg PBTB 3687' with top perf. (3584')~~

7" csg bridged at 3518' -Dumped 6 sk cem. W/dump bailer.

No pipe recovered.

Set 7" wood plug at 695' -poured sand & rock (675-695)

Pumped down 7" csg with 25 sk cem. -- 5 sk gel & water -- capped with 25 sk cem.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/5/73

INV. NO. 8119-10

Signed: Bud A. Mearns  
Well Plugging Supervisor