

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 5 1973

CONSERVATION DIVISION  
Wichita, Kansas

11-05-73

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company  
Complete Address 217 N. Water Wichita, Kansas 67202  
Lease Name C. A. Desbien Well No. 6  
Location NW SE NW Sec. 12 Twp. 10 Rge. (E) (W) 20  
County Rooks Total Depth 3784'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Kelso Pipe Pulling  
Address Box 176 Chase, Kansas 67524 License No. 683  
Operation Completed: Hour 12:45 P Day 1 Month 11 Year 1973

The above well was plugged as follows:

Total Depth 3784' 10 3/4 csg set at 360' cwc 225 sk.

5 1/2 csg set at 3776' cw 200 sk cmt.

Filled 5 1/2 csg W/sd (3750-3784) dumped 5 sk cmt W/dump bailer. (3715-3750)

Cutoff and recovered 1008' of 5 1/2 csg.

Pumped down 10 3/4 csg with 15 sk gel & water W/500 lbs hulls -- 50 sk cem. -- 10 sk gel & water -- released 10 3/4 plug and pumped 70 sk cem. Max PP 800 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/5/73

INV. NO. 8121-W

Signed: Brent Massey  
Well Plugging Supervisor