

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-133- D1676-00-00
sw nw ~~SW~~ SE NE Sec/Twp/Rge 33-28-21E
3552 (GPS) feet from south section line
2375 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Vanleeuwen GPS #08

Operator: State Of Kansas Fee Fund

County Neosho

Well Total Depth 450 (est) feet

Name & Dent/Vanleeuwen Lease Project

Production Pipe: 2 Size Feet 450 (est)

Address _____

Surface Casing: 6 Size Feet NA

AB oil well _____ Gas Well _____

SWD Well/ Input Well E-04612.10 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 27 Month: 10 2008

Plugging proposal received from: Mike Kepley

Company Name: _____ Phone: _____

Were: Clean well to TD and then pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All _____ Part _____ None XXXXXX

TECHNICIAN

Operations Completed: Hour: _____ Day: 27 Month: 10 2008

Actual Plugging Report: 400' of 1" pipe with packer were pulled. The well was then perforated at 300' and 150'. A 1" cement string was lowered to 400' inside the 2" production pipe. The well was then pumped full of cement from btm to top thru this cement string. A total of 21 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control #20080018-035

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

Signed:

Alan M. Dunning
TECHNICIAN

NOV 10 2008