

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-133- 01677-00-00
NW SW NE Sec/Twp/Rge 33-28-21E
3352 (GPS) feet from south section line
2313 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: State Of Kansas Fee Fund
Name & Dent/Vanleeuwen Lease Project
Address _____

Lease/Well# Vanleeuwen GPS #09
County Neosho
Well Total Depth 450 (est) feet
Production Pipe: 5.5 Size Feet 415
Surface Casing: 8 Size Feet NA
SWD Well/ Input Well _____ D & A _____

AB oil well XXXXXX Gas Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749
Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 25 Month: 9 2008

Plugging proposal received from: Mike Kepley

Company Name: _____ Phone: _____

Were: Clean well to TD and then pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All XXXXXX Part _____ TECHNICIAN
None _____

Operations Completed: Hour: _____ Day: 25 Month: 9 2008

Actual Plugging Report: A 1" cement string was washed down the inside of the 5.5" production pipe to 415'. A 1" cement string was washed down the outside of the 5.5" production pipe to 200'. The well was then pumped full of cement from btm to top thru these cement strings. A total of 117 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control #20080018-036
(If additional description is necessary, use BACK of this form.)

I did observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

Signed:

Alan M. Dunning
TECHNICIAN

OCT 16 2008

CONSERVATION DIVISION
WICHITA, KS