

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-133-01180-00-00
SW NW NE Sec/Twp/Rge 33-28-21E
4407 (GPS) feet from south section line
2077 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Vanleeuwen GPS #13

Operator: State Of Kansas Fee Fund

County Neosho

Well Total Depth 450 (est) feet

Name & Dent/Vanleeuwen Lease Project

Production Pipe: 2 Size Feet 450(est)

Address _____

Surface Casing: 4.5 Size Feet NA

AB oil well XXXXXX Gas Well _____

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 4 Month: 11 2008

Plugging proposal received from: Mike Kepley

Company Name: _____ Phone: _____

Were: Clean well to TD and then pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXX

Operations Completed: Hour: _____ Day: 4 Month: 11 2008

Actual Plugging Report: 250' of the 1.875" poly pipe was removed. The well was then perforated at 250' and 150'. A 1" cement string was lowered to 275' and the well pumped full of cement from btm to top thru this cement string. A total of 14 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 11 2008

Remarks: Control #20080018-040 CONSERVATION DIVISION
(If additional description is necessary, use BACK of this form.) WICHITA, KS

I did not observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN