

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-133-01681-00-00  
SW NW NE Sec/Twp/Rge 33-28-21E  
4159 (GPS) feet from south section line  
2095 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 101  
Operator: State Of Kansas Fee Fund  
Name & Dent/Vanleeuwen Lease Project  
Address \_\_\_\_\_

Lease/Well# Vanleeuwen GPS #14  
County Neosho  
Well Total Depth 450 (est) feet  
Production Pipe: 4 Size Feet 450 (est)  
Surface Casing: 8 Size Feet NA

AB oil well XXXXX Gas Well \_\_\_\_\_

SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: \_\_\_\_\_ Day: 28 Month: 8 2008

Plugging proposal received from: Mike Kepley

Company Name: \_\_\_\_\_ Phone: \_\_\_\_\_

Were: Clean well to TD and pump full of cement from btm to top thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXX  
TECHNICIAN

Operations Completed: Hour: \_\_\_\_\_ Day: 28 Month: 8 2008

Actual Plugging Report: A 3" swedge was lowered to 390'. The swedge was pulled out so the well could be perforated. The well was perforated at 250' and 150'. A one inch cement string was lowered to 375' and the well pumped full of cement. A total of 59 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 24 2008

Remarks: Control # 0080018-041 CONSERVATION DIVISION  
(If additional description is necessary, use BACK of this form.) WICHITA, KS

I did not observe this plugging.

Signed:

Alan M. Dunning  
TECHNICIAN