

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-133-01685-00-00  
NE SW NE Sec/Twp/Rge 33-28-21E  
3424 (GPS) feet from south section line  
1376 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Vanleeuwen GPS #20

Operator: State Of Kansas Fee Fund

County Neosho

Name & Dent/Vanleeuwen Lease Project

Well Total Depth 450 (est) feet

Address \_\_\_\_\_

Production Pipe: 2 Size Feet 450 (est)

AB oil well XXXXXX Gas Well \_\_\_\_\_

Surface Casing: 6 Size Feet NA

SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: \_\_\_\_\_ Day: 17 Month: 9 2008

Plugging proposal received from: Mike Kepley

Company Name: \_\_\_\_\_ Phone: \_\_\_\_\_

Were: Clean well to TD, perforate, and then pump full of cement from btm to top thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All XXXXXX Part \_\_\_\_\_ None \_\_\_\_\_

TECHNICIAN

Operations Completed: Hour: \_\_\_\_\_ Day: 17 Month: 9 2008

Actual Plugging Report: A reamer on a 1" pipe was ran to 410' where the pipe hit solid. The reamer was removed. The well was perforated at 250' and 150'. A 1" cement string was lowered to 400' and the well plugged from btm to top thru this cement string. A total of 33 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 09 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: Control #20080018-047

(If additional description is necessary, use BACK of this form.)

I did observe this plugging.

Signed: Alan M. Dunning  
TECHNICIAN