

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-133-01686-00-00
NW SE NE Sec/Twp/Rge 33-28-21E
3388 (GPS) feet from south section line
1075 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Vanleeuwen GPS #21

Operator: State Of Kansas Fee Fund

County Neosho

Well Total Depth 450 (est) feet

Name & Dent/Vanleeuwen Lease Project

Production Pipe: 2 Size Feet 450 (est)

Address _____

Surface Casing: NA Size Feet NA

AB oil well _____ Gas Well _____

SWD Well/ Input Well E-04612.13 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 18 Month: 9 2008

Plugging proposal received from: Mike Kepley

Company Name: _____ Phone: _____

Were: Clean well to TD, perforate, and then pump full of cement from btm to top thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All _____ Part _____ None XXXXXX

TECHNICIAN

Operations Completed: Hour: _____ Day: 18 Month: 9 2008

Actual Plugging Report: The 1" pipe and packer were removed. The well was then perforated at 250' and 150'. A 1" cement string was lowered to 350' and the well filled with cement from btm to top thru this cement string. A total of 38 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 09 2008

Remarks: Control # 20080018-048
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
WICHITA, KS

I did not observe this plugging.

Signed: Alan M. Dunning
TECHNICIAN