

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-133-01692-00-00
NW SE NE Sec/Twp/Rge 33-28-21E
3759 (GPS) feet from south section line
679 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: State Of Kansas Fee Fund
Name & Dent/Vanleeuwen Lease Project
Address _____

Lease/Well# Vanleeuwen GPS #27
County Neosho
Well Total Depth 450 (est) feet
Production Pipe: 2 Size Feet 450 (est)
Surface Casing: NA Size Feet NA

AB oil well XXXXXX Gas Well _____

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: _____ Hour: _____ Day: 18 Month: 9 2008

Plugging proposal received from: Mike Kepley

Company Name: _____ Phone: _____

Were: Clean well to TD, perforate, and then pump full of cement from btm to top thru cement string.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All XXXXXX Part _____ None _____

Operations Completed: Hour: _____ Day: 18 Month: 9 2008

Actual Plugging Report: A reamer on a 1" pipe was ran to 385' where the pipe hit solid. The reamer was removed. The well was perforated at 250' and 150'. A 1" cement string was lowered to 375' and the well plugged from btm to top thru this cement string. A total of 19 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 09 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: Control #20080018-054

(If additional description is necessary, use BACK of this form.)

I did observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN