

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-133-01694-00-00  
NW SE NE Sec/Twp/Rge 33-28-21E  
3789 (GPS) feet from south section line  
850 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 101  
Operator: State Of Kansas Fee Fund  
Name & Dent/Vanleeuwen Lease Project  
Address \_\_\_\_\_

Lease/Well# Vanleeuwen GPS #31  
County Neosho  
Well Total Depth 450 (est) feet  
Production Pipe: 2 Size Feet 450 (est)  
Surface Casing: 6 Size Feet NA

AB oil well \_\_\_\_\_ Gas Well \_\_\_\_\_

SWD Well/ Input Well E-04612.7 D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: \_\_\_\_\_ Hour: \_\_\_\_\_ Day: 19 Month: 9 2008

Plugging proposal received from: Mike Kepley

Company Name: \_\_\_\_\_ Phone: \_\_\_\_\_

Were: Clean well to TD, perforate, and then pump full of cement from btm to top thru cement string.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXX

Operations Completed: Hour: \_\_\_\_\_ Day: 19 Month: 9 2008

Actual Plugging Report: 360' of the 1" pipe was removed. A 1" pipe with reamer was ran to 380'.

The 1" pipe and reamer were removed and the well perforated at 250' and 150'. A 1" cement string was lowered to 375' and the well filled from btm to top thru this cement string. A total of 20 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 09 2008

Remarks: Control # 20080018-058

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
WICHITA, KS

I did not observe this plugging.

Signed:

Alan M. Dunning  
TECHNICIAN