

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-133-01695-00-00
NE SW NE Sec/Twp/Rge 33-28-21E
3357 (GPS) feet from south section line
1486 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Vanleeuwen GPS #32

Operator: State Of Kansas Fee Fund

County Neosho

Name & Dent/Vanleeuwen Lease Project

Well Total Depth 450 (est) feet

Address _____

Production Pipe: 2 Size Feet 450 (est)

AB oil well _____ Gas Well _____

Surface Casing: NA Size Feet NA

SWD Well/ Input Well E-04612.12 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: _____ Hour: _____ Day: 17 Month: 9 2008

Plugging proposal received from: Mike Kepley

Company Name: _____ Phone: _____

Were: Clean well to TD, perforate, and then pump full of cement from btm to top thru cement string.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All XXXXXX Part _____ None _____

Operations Completed: Hour: _____ Day: 17 Month: 9 2008

Actual Plugging Report: A 1" pipe with reamer was lowered to 410'. The 1" pipe and reamer were removed and the well perforated at 250' and 150'. A 1" cement string was then lowered to 400' and the well filled from btm to top thru this cement string. A total of 27 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 09 2008

Remarks: Control # 20080018-059
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
WICHITA, KS

I did observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN