

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-133-01697-00-00
SE NW NE Sec/Twp/Rge 33-28-21E
4225 (GPS) feet from south section line
1626 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: State Of Kansas Fee Fund
Name & Dent/Vanleeuwen Lease Project
Address _____

Lease/Well# Vanleeuwen GPS #36
County Neosho
Well Total Depth 450 (est) feet
Production Pipe: 2 Size Feet 342
Surface Casing: 6 Size Feet NA
SWD Well/ Input Well _____ D & A _____

AB oil well XXXXXX Gas Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749
Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 3 Month: 9 2008

Plugging proposal received from: Mike Kepley

Company Name: _____ Phone: _____

Were: Clean well to TD and pump full of cement from btm to top thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All _____ Part _____ None XXXXXX
TECHNICIAN

Operations Completed: Hour: _____ Day: 3 Month: 9 2008

Actual Plugging Report: The 2" production pipe was removed. The well still contains a 4" string of pipe. The well was perforated at 250' and 150'. A 1" cement string was lowered to 440' The well was pumped full of cement from btm to top thru this cement string. A total of 65 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 17 2008

Remarks: Control # 0080018-063
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
WICHITA, KS

I did not observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN