

3 023236

15-001-02919-00-00

To:

API NUMBER 20080002-002

STATE CORPORATION COMMISSION

NE,NE,NE 1/4 Sec/Twp/Rge S.23-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

4991 feet from south section line

130 S. Market, Room 2078

382 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# WEINER NO. GG-19

Operator License # 100101

County ALLEN

Operator: STATE OF KANSAS

Well Total Depth 850 feet

Name &amp; FEE FUND PLUGGING

Production Pipe: 2" Size Feet 850

Address

Surface Casing: 8" Size Feet 20'

AB oil well Gas Well SWD Well/ Input Well

E-00591 D &amp; A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30870

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: 31 Month: 10 2007

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT HAD

'BEEN CEMENTED IN AT EVIDENTLY FROM BOTTOM TO TOP. A STUMP OF 1" PIPE

IS IN THE WELL FROM 440' TO APPROX. 800. THE PLUGGING PROPOSAL IS TO

CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part

TECHNICIAN

None X

Operations Completed: Hour: 11:00A.M. Day: 31 Month: 10 2007

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 425'. CEMENT

WAS PUMPED INTO THE 1" TUBING UNTIL CEMENT CIRCULATED FROM THE WELL AT

SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

63 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED

NOV 19 2007

Remarks: (GPS SESSION POINT NO. 02) (THIS WAS NO. GG-19 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I DID NOT observe this plugging.

Signed:


  
TECHNICIAN

