

3 023232

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 100101Operator: STATE OF KANSASName & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC.

Lic. #

30670 **33749**Address: 19245 FORD RD., CHANUTE, KS. 66720Company to plug at: Hour: 8:00A.M. Day: _____ 9 Month: 11 2007Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT HADBEEN CEMENTED IN FROM T.D. TO APPROXIMATELY 225'. THE PLUGGING PROPOSALWAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____

TECHNICIAN

None ☒ XOperations Completed: Hour: 12:00P.M. Day: _____ 9 Month: 11 2007Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 725'. CEMENT WASPUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE.THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 225'. ATTHAT DEPTH A SOLID OBSTRUCTION WAS ENCOUNTERED. CEMENT WAS PUMPED INTOTHE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 91 SACKS OF CEMENTWERE PUMPED INTO THIS WELL.Remarks: GPS SESSION POINT NO. WEI 4. (THIS WAS WELL NO. DD-18 ON THE LEASE MAP.)(If additional description is necessary, use BACK of this form.)I ☐ DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN**RECEIVED****NOV 19 2007****KCC WICHITA****PFT**