

3 023257

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER

15-001-02426-00-00

20080002-011009

SW,NE,NE 1/4

Sec/Twp/Rge S.23-T.26S-18E.

4481 feet from south section line

883 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

WEINER NO.DD-20

Operator License #

106(01)

County

ALLEN

Operator: STATE OF KANSAS

Well Total Depth 850'

feet

Name & FEE FUND PLUGGING

Production Pipe: 2"

Size Feet 850'

Address

Surface Casing: 8"

Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐D & A ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC.

Lic. #

30670

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: 29 Month: 11 2007

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT MAY

HAVE BEEN CEMENTED IN AT T.D. ONLY. THE 2" AND 8" ANNULUS WAS OBSTRUCTED.

THE PLUGGING PROPOSAL WAS TO PERFORATE THE 2" CASING SEVERAL TIMES AND

TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All ☐Part ☐

TECHNICIAN

None ☐X ☒

Operations Completed: Hour:

12:00P.M. Day:

29 Month:

11

2007

Actual Plugging Report:

THE 2" CASING WAS PERFORATED AT 700' AND WAS

PERFORATED AT 200'. 1" PIPE WAS RAN INTO THE 2" CASING TO 725'. CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED

JAN 31 2008

Remarks: GPS SESSION POINT NO. WEI 11. (THIS WAS WELL NO. DD-20 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

pk