

plugging contractor  
expired. please  
correct & return  
with original  
signature

23425

COMMISSION

- PLUGGING SECTION

'8

15-001-02490-00-00

API NUMBER 20080046-046

NE,NE,SE 1/4 Sec/Twp/Rge S.14-T.26S.-R.18E.

1093 25 feet from south section line

179 1600 feet from east section line

*[Handwritten signature]*

TECHNICIAN'S PLUGGING REPORT

Operator License # 100101

Operator: STATE OF KANSAS

Name & FEE FUND PLUGGING

Address

AB oil well X Gas Well SWD Well/ Input Well

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30670

33749

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 1:00P.M. Day: 31 Month: 7 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL ORIGINALLY CONSISTED OF 2" CASING TO 850' THAT HAD

BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All X Part

TECHNICIAN  
None

Operations Completed: Hour: 4:00P.M. Day: 31 Month: 7 2008

Actual Plugging Report: 740' OF 1" PIPE WAS FISHED FROM THE WELL. 3/4"

PIPE WAS RAN INTO THE 2" CASING TO 740'. CEMENT WAS PUMPED INTO THE 3/4"

PIPE UNTIL CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE 3/4" PIPE

WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 500'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE

CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED

FROM SURFACE. 226 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. 3) (THIS WELL WAS NO. HH-4 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 25 2008

CONSERVATION DIVISION  
WICHITA KS

Signed:

*[Handwritten signature]*  
TECHNICIAN

*[Handwritten signature]*