

3 023335

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER

15-001-02387-00-00

2008004051

SE,NE,SE 1/4

Sec/Twp/Rge S.14-T.26S.-R.18E.

1360 feet from south section line

42 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

NORDT NO. II-9

Operator License #

100101

County

ALLEN

Operator: STATE OF KANSAS

Well Total Depth

850 feet

Name & FEE FUND PLUGGING

Production Pipe: 2"

Size Feet

850

Address

Surface Casing: 8"

Size Feet

20'

AB oil well

Gas Well

SWD Well/ Input Well

E-591

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30870

33749

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at:

Hour:

8:00A.M.

Day:

24 Month:

3

2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name:

KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were:

THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT HAD

BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All

X

Part

TECHNICIAN

None

Operations Completed: Hour:

12:00P.M.

Day:

24 Month:

3

2008

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 760'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8"

ANNULUS TO 350'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED

FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT

WAS FILLED FROM SURFACE. 115 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED

KANSAS CORPORATION COMMISSION

APR 14 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: (GPS SESSION POINT NO. 08) (THIS WAS WELL NO II-9 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I

DID

observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

PST