

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 19648-00-00
SE SE NW Sec/Twp/Rge Sec 14 T27S R15E
3191 (GPS) feet from south section line
2844 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101

Lease/Well# Milligan GPS # 01
County Wilson

Operator: State Of Kansas Fee Fund

Well Total Depth 1050 feet

Name & Milligan (Claiborne) Lease Project

Production Pipe: 4.5" Size Feet 1050

Address _____

Surface Casing: 8 Size Feet NA

AB oil well _____ Gas Well XXXXXX

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 16 Month: 7 2008

Plugging proposal received from: Sam Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Wash well to TD and fill from btm to top with portland cement thru one inch cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All _____ Part _____ None XXXXXX TECHNICIAN

Operations Completed: Hour: _____ Day: 16 Month: 7 2008

Actual Plugging Report: A one inch cement string was lowered down the inside of the 4.5" pipe to

1050'. A one inch cement string was washed down the outside of the 4.5" pipe to 10' where the cement

string hit cement. The well was plugged from btm to top thru these cement strings. A total of 98 sacks of

portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control # 20080068-001

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 21 2008
CONSERVATION DIVISION
WICHITA, KS

Signed:

Alan M. Dunning
TECHNICIAN