

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 19654-00-00
SE NW SW Sec/Twp/Rge Sec 10, T29S, R17E
1613 (GPS) feet from south section line
4148 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Martin (Stich) GPS # STI-13

Operator: State Of Kansas Fee Fund

County Wilson

Name & Martin (Stich) Lease Project

Well Total Depth 700 (est) feet

Address _____

Production Pipe: 2 Size Feet 700

AB oil well XXXXXXX Gas Well _____

Surface Casing: NA Size Feet NA

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 25 Month: 1 2008

Plugging proposal received from: Sam Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Wash well to TD and fill from btm to top with portland cement.

_____ Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All _____ Part _____ None XXXXXX

TECHNICIAN

Operations Completed: Hour: _____ Day: 25 Month: 1 2008

Actual Plugging Report: 9' of 8" surface pipe was set to bring well to surface. A one inch cement string was washed to 300' inside the 2" where cement was encountered. The 2" pipe was perforated at 75', 150', and 250'. A one inch cement string was then washed to 700' inside the 2" pipe. The well was plugged from btm to top thru this cement string. A total of 21 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 05 2008

Remarks: Control # 20080015-013
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
WICHITA, KS

I did not observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN