

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205-19655-00-00
SE NW SW Sec/Twp/Rge Sec 10, T29S, R17E
1378 (GPS) feet from south section line
4540 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Lease/Well# Martin (Stich) GPS # STI-15County WilsonOperator: State Of Kansas Fee FundWell Total Depth 750 feetName & Martin (Stich) Lease ProjectProduction Pipe: 2 Size Feet 750

Address _____

Surface Casing: 4 Size Feet NAAB oil well XXXXXXX Gas Well _____

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, IncLic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: Hour: _____ Day: 15 Month: 1 2008Plugging proposal received from: Sam KepleyCompany Name: K-W Oil Well Service, IncPhone: 620-433-7730Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: _____

Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXXOperations Completed: Hour: _____ Day: 15 Month: 1 2008

Actual Plugging Report: A 1" cement string was washed to 300'. The well was then perforated at 75', 150', and 250'. A 1" cement string was lowered to 750' inside the 2" pipe. The well was plugged from btm to top thru this cement string. A total of 35 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 05 2008

Remarks: Control # 20080015-015

CONSERVATION DIVISION
WICHITA, KS

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed: _____

Alan M. Dunning
TECHNICIAN