

3 023451

15-001-02492-00-00

To:

API NUMBER 20090010-002

STATE CORPORATION COMMISSION

SW,NW,NW 1/4 Sec/Twp/Rge S.3-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

4406 feet from south section line

130 S. Market, Room 2078

4986 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# CITY OF HUMBOLDT NO. 2

Operator License # 101

County ALLEN

Operator: STATE OF KANSAS

Well Total Depth 850 feet

Name & FEE FUND PLUGGING

Production Pipe: Size Feet

Address

Surface Casing: 8" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: K W OIL WELL SERVICE, INC.

Lic. # 3097

Address: 19450 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 1:00P.M. Day: 14 Month: 10 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: VISIBLE AT SURFACE ON THIS WELL WAS 8" SURFACE CASING ONLY. THE

PLUGGING PROPOSAL WAS TO DRILL OUT AS MUCH OF THE WELL AS POSSIBLE AND

TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

RECEIVED

NOV 17 2008

Plugging Proposal Received by:

CLAYTON P. TITEL

TECHNICIAN

Plugging attended by Agent: All ☒ Part

None

Operations Completed: Hour: 3:00P.M. Day: 14 Month: 10 2008

Actual Plugging Report: THE WELL WAS DRILLED OUT TO 500'. AT THAT DEPTH

IRON WAS ENCOUNTERED. 1" PIPE WAS RAN INTO THE WELL TO 510'. CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING

AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM

SURFACE. 147 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. 2)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN