

3 023399

15-001-02494-00-00

To:

API NUMBER 20080016-001

STATE CORPORATION COMMISSION

NE,SW,SW 1/4 Sec/Twp/Rge S.31-T.26S.-R.19E.

Wichita State Office Bldg. - PLUGGING SECTION

1051 feet from south section line

130 S. Market, Room 2078

4194 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# FEWINS NO.1

Operator License # 100

County ALLEN

Operator: STATE OF KANSAS

Well Total Depth 850 feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 850

Address

Surface Casing: 7" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A

Other well as hereinafter indicated:

Plugging Contractor: K-W OIL WELL SERVICE INC.

Lic. # 3097

Address: 19450 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00 A.M. Day: 2 Month: 7 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: VISIBLE ON THIS WELL WAS 1" PIPE, IN 2" PIPE, IN 4" PIPE IN 7" PIPE. 650' OF 1"

WAS PULLED. THE PLUGGING PROPOSAL WAS TO PERFORATE THE 2" AND 4" AND TO

CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

TECHNICIAN

Plugging attended by Agent: All ☐ Part ☒None ☐

Operations Completed: Hour: 12:00 P.M. Day: 2 Month: 7 2008

Actual Plugging Report: THE CASINGS WERE PERFORATED AT 350' AND AT 150'.

1" PIPE WAS RAN INTO THE 2" CASING TO 650'. CEMENT WAS PUMPED INTO THE 1"

PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AND 4" CASING AND 7" SURFACE

CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM

SURFACE. 91 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. FEW 01) (NO MAP WAS AVAILABLE.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

Signed:

JUL 18 2008

CONSERVATION DIVISION
WICHITA, KSClayton P. Titel
TECHNICIAN

PK7