

3 023400

15-001-02995-00-00

To:

API NUMBER 20080016-002

STATE CORPORATION COMMISSION

NW 1/4, SW 1/4 Sec/Twp/Rge S.31-T.26S.-R.19E.

Wichita State Office Bldg. - PLUGGING SECTION

1983 feet from south section line

130 S. Market, Room 2078

4946 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# FEWINS NO.2

Operator License # 100

County ALLEN

Operator: STATE OF KANSAS

Well Total Depth 850 feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 850

Address

Surface Casing: 7" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A

Other well as hereinafter indicated:

Plugging Contractor: K-W OIL WELL SERVICE INC.

Lic. # 3097

Address: 19450 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00 A.M. Day: 24 Month: 6 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT HAD

BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO

CIRCULATED THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part ☐TECHNICIAN
None

Operations Completed: Hour: 9:30 A.M. Day: 24 Month: 6 2008

Actual Plugging Report: 1" TUBING WAS RAN INTO THE 2" CASING TO 750'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE

2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS

FILLED FROM SURFACE. 28 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. FEW 02) (NO MAP WAS AVAILABLE.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

Signed:

JUL 18 2008

CONSERVATION DIVISION
WICHITA, KSClayton P. Titel
TECHNICIAN

PK5