

3 023402

15-001-02497-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER 20080016-004

NW,SW,SW 1/4 Sec/Twp/Rge S.31-T.26S.-R.19E.

2326 feet from south section line

4944 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 100

Operator: STATE OF KANSAS

Name & FEE FUND PLUGGING

Address

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

Other well as hereinafter indicated:

Plugging Contractor: K-W OIL WELL SERVICE INC.

Lic. # 3097

Address: 19450 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 1:00 P.M. Day: 24 Month: 6 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 850' THAT HAD

BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO

CIRCULATE THE 2 7/8" CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part ☐

TECHNICIAN

None ☐

Operations Completed: Hour: 3:00 P.M. Day: 24 Month: 6 2008

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2 7/8" CASING TO 750'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE

2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS

FILLED FROM SURFACE. 100 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. FEW 04) (NO MAP WAS AVAILABLE.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION
Signed:

JUL 18 2008

CONSERVATION DIVISION
WICHITA, KSClayton P. Titel
TECHNICIAN

Pkg