

3 023403

15-001-02498-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER 20080016-005

NE,NW,SW 1/4 Sec/Twp/Rge S.31-T.26S.-R.19E.

2598 feet from south section line

4525 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 100

Operator: STATE OF KANSAS

Name & FEE FUND PLUGGING

Address

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: K-W OIL WELL SERVICE INC.

Lic. # 3097

Address: 19450 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00 A.M. Day: 26 Month: 6 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 " CASING TO APPROXIMATELY 850' THAT HAD

BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☐ Part ☒TECHNICIAN
None ☐

Operations Completed: Hour: 12:00 P.M. Day: 26 Month: 6 2008

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2 " CASING TO 550'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE

2 " CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE

2" AND 8" ANNULUS TO 650'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT

CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED.

DISPLACEMENT WAS FILLED FROM SURFACE. 214 SACKS OF CEMENT WERE

PUMPED INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. FEW 05) (NO MAP WAS AVAILABLE.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION Signed:

JUL 18 2008

CONSERVATION DIVISION
WICHITA, KSClayton P. Titel
TECHNICIAN