

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078
Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: State Of Kansas Fee FundName & Safari Golf Course Lease Project

Address _____

AB oil well _____ Gas Well XXXXXX

It is estimated that this well was drilled in the 1950's

API NUMBER 15-133-01564-00-00

SW SW SE Sec/Twp/Rge Sec 32 T27S R18E

180 (GPS) feet from south section line

2375 (GPS) feet from east section line

Lease/Well# Safari Golf Course OW-1County NeoshoWell Total Depth 525 (est) feetProduction Pipe: N/A Size Feet N/ASurface Casing: N/A Size Feet N/A

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: Hour: _____ Day: 1 Month: 10 2007Plugging proposal received from: Jim KepleyCompany Name: K-W Oil Well Service, Inc Phone: 620-496-7173Were: Wash well to TD and then fill from btm to top with cement.Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All XXXXXX Part _____ None _____Operations Completed: Hour: _____ Day: 1 Month: 10 2007Actual Plugging Report: 9-24-07: 20 ft of 10" surface pipe was set.9-27-07 thru 10-1-07: Used drilling rig to drill to 510 ft where the rig hit iron.10-1-07: A one inch cement string was washed down to 525 ft. The well was plugged from btm to top thru this cement string. A total of 162 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.RECEIVED
KANSAS CORPORATION COMMISSION

NOV 09 2007

Remarks: Control # 2008022-001CONSERVATION DIVISION
WICHITA, KS

(If additional description is necessary, use BACK of this form.)

I did observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN

53