

15-205-19465-00-00

3 023120

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20070001-030
^{SW} SW, ~~SE~~ NE 1/4 Sec/Twp/Rge S.3-T.27S.-R.16E.
2721 feet from south section line
2037 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 100 101
Operator: STATE OF KANSAS
Name & BUFFALO III FEE FUND
Address PLUGGING PROJECT

Lease/Well# FOSTER NO.2-I
County WILSON
Well Total Depth 950' feet
Production Pipe: 2" Size Feet 950'
Surface Casing: 6" Size Feet 20'

AB oil well _____ Gas Well _____ SWD Well/ Input Well E-4207 D & A _____
Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING & ROUSTABOUT SERVICE Lic. # 6372
Address: P.O. BOX 386, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:00A.M. Day: _____ Month: 1 2007

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 950' THAT HAD
BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS
MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE 2"
CASING.

Plugging Proposal Received by: CLAYTON P. TITEL
TECHNICIAN
Plugging attended by Agent: All _____ Part X None _____

Operations Completed: Hour: 12:30P.M. Day: _____ Month: 1 2007

Actual Plugging Report: 1" PIPE WAS FISHED FROM THE WELL TO 600'. 1" PIPE
WAS RAN INTO THE 2' CASING TO 600'. CEMENT WAS PUMPED INTO THE 1' PIPE UNTIL
CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1' PIPE WAS REMOVED.
1" PIPE WAS WASHED INTO THE 2" AND 6' ANNULUS TO 225'. AT THAT DEPTH A SOLID
OBSTRUCTION WAS ENCOUNTERED. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL
CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1' PIPE WAS
REMOVED. 66 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.30) (THIS WAS WELL NO.2-I ON THE LEASE MAP.)
(If additional description is necessary, use BACK of this form.)

I did observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

KANSAS CORPORATION COMMISSION

JAN 2 2 2007

CONSERVATION DIVISION
WICHITA, KS

6

PCT