

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24187-00-01

Spot: SESENE

Sec/Twnshp/Rge: 5-14S-16W

2970 feet from S Section Line, 330 feet from E Section Line

Lease Name: TED

Well #: 1

County: ELLIS

Total Vertical Depth: 3455 feet

Operator License No.: 101

Op Name: KCC FEE FUND PLUG

Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3499	0	w/125 sxs cmt
SURF	8.625	209	0	w/135 sxs cmt

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/23/2009 10:00 AM

Plug Co. License No.: 3152

Plug Co. Name: POE SERVICING INC

Proposal Rcvd. from: ED POE

Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 4% gel.
PC at 1018' w/295 sxs.
Well was plugged on 01/17/1996. Cement fell back - backside not checked.

CN 20080060001

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/23/2009 3:00 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Poe rigged up and RIH with tubing to 868'.
Allied rigged to tubing and pumped 85 sxs 60/40 pozmix - 4% gel to circulate cement to pit area.
Pulled tubing - rigged to 4 1/2" casing with a swedge and pumped 15 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.
Dug out 8 5/8" - backside was full - visual check.

Perfs:

Top	Bot	Thru	Comments
3386	3388		
3358	3360		
3267	3269		
3203	3206		

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 26 2009

Remarks: ALLIED CEMENTING COMPANY-TICKET #36282.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

Form CP-2/3

MAR 24 2009