

3 023195

15-2017-02009-20-00

To:

API NUMBER ~~20070029-030~~

STATE CORPORATION COMMISSION

SE

SW,NW,NE 1/4 Sec/Twp/Rge S.21-T.26S.-R.16E.

Wichita State Office Bldg. - PLUGGING SECTION

4074 feet from south section line

130 S. Market, Room 2078

2054 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

Rose East - Toedman A 4
TOEDMAN 04

Operator License #

100 101

County

WOODSON

Operator: STATE OF KANSAS

Well Total Depth 1100' feet

Name & FEE FUND PLUGGING

Production Pipe: 4 1/2" Size Feet 1100'

Address

Surface Casing: 6" Size Feet 40'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30670

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 1:00P.M. Day: 3 Month: 8 2007

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 1100' THAT MAY

HAVE BEEN CEMENTED IN FROM BOTTOM TO TOP. THE 4 1/2" CASING WAS OBSTRUCTED

WITH IRON AT 70'. THE PLUGGING PROPOSAL WAS TO FILL AS MUCH OF THE WELL AS

POSSIBLE WITH CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

TECHNICIAN

Plugging attended by Agent: All ☒ Part ☐None ☐

Operations Completed: Hour: 3:00P.M. Day: 3 Month: 8 2007

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 4 1/2" PIPE TO 70'. AT THAT

POINT PROGRESS WAS HALTED BY IRON. CEMENT WAS PUMPED INTO THE 1" PIPE

UNTIL CEMENT CIRCULATED FROM THE 4 1/2" AT SURFACE. THE 1" WAS REMOVED.

DISPLACEMENT WAS FILLED FROM SURFACE. THE PUMP TRUCK WAS CONNECTED

DIRECTLY TO THE 4 1/2" CASING. THE WELL WAS THEN PRESSURED UP TO 700P.S.I..

28 SACKS OF CEMENT WERE PUMPED INTO THIS WELL/

Remarks: (SPOT LOCATION ESTABLISHED BY GPS AS TOE 4)

Control # 20070029-030

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel

TECHNICIAN RECEIVED

KANSAS CORPORATION COMMISSION

AUG 20 2007

CONSERVATION DIVISION
WICHITA, KS