

3 023189

15-207-02012-00-00

To:

API NUMBER 20070029-041

STATE CORPORATION COMMISSION

NW SW,NE,SE 1/4 Sec/Twp/Rge S.21-T.26S.-R.16E.

Wichita State Office Bldg. - PLUGGING SECTION

1858 feet from south section line

130 S. Market, Room 2078

1204 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

Rose East - Toedman C 1
TOEDMAN C NO. 1

Operator License #

100

County

WOODSONOperator: STATE OF KANSASWell Total Depth 800' feetName & FEE FUND PLUGGINGProduction Pipe: 4 1/2" Size Feet 800'

Address

Surface Casing: 6" Size Feet 40'AB oil well X Gas Well SWD Well/ Input Well D & A Other well as hereinafter indicated: Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30670Address: 19245 FORD RD., CHANUTE, KS. 66720Company to plug at: Hour: 8:00A.M. Day: 11 Month: 7 2007Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 800' THAT HAD'BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO PERFORATE THE4 1/2" CASING AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All Part

TECHNICIAN

None X

Operations Completed: Hour:

5:00P.M.Day: 11 Month:

7

2007

Actual Plugging Report:

THE 4 1/2" CASING WAS PERFORATED AT 700' AND WASPERFORATED AT 200'. 1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 800'. CEMENT WASPUMPED INTO THE 4 1/2" CASING UNTIL CEMENT CIRCULATED FROM BOTH THE 4 1/2"CASING AND FROM THE 4 1/2" AND 6" ANNULUS AT SURFACE. THE 1' PIPE WAS REMOVEDDISPLACEMENT WAS FILLED FROM SURFACE. 372 SACKS OF CEMENT WERE PUMPEDINTO THIS WELL.Remarks: (SPOT LOCATION ESTABLISHED BY GPS AS TOC 01)Control # 20070029-041(If additional description is necessary, use BACK of this form.)I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIANRECEIVED
KANSAS CORPORATION COMMISSION

AUG 20 2007

CONSERVATION DIVISION
WICHITA, KS