

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-059-01084-00-00
NE NE NE Sec/Twp/Rge 29-16S-21E
4633 feet from south section line
281 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: STATE OF KANSAS
Name & FEE FUND
Address CHANUTE DISTRICT OFFICE

Lease/Well# LAWSON # LAW70
County FRANKLIN
Well Total Depth 500 feet
Production Pipe: 2 Size Feet 500
Surface Casing: 8 Size Feet EST 20
AB oil well XXXXXXX Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W OIL WELL SERVICE, INC. Lic. # 3097
Address: 19450 FORD ROAD, CHANUTE, KS 66720

Company to plug at: Hour: _____ Day: 14 Month: JUNE 2007

Plugging proposal received from: SAM KEPLEY

Company Name: K-W OIL WELL SERVICE, INC. Phone: (620) 496-7173

Were: FILL WELL WITH CEMENT FROM TD TO SURFACE.

Plugging Proposal Received by: LEVI SHORT

Plugging attended by Agent: All _____ Part _____ TECHNICIAN
None XXXXXXX

Operations Completed: Hour: _____ Day: 14 Month: JUNE 2007

Actual Plugging Report: RUN 3/4 INCH INSIDE 2 INCH CASING TO 500 FEET AND RUN 1 INCH
OUTSIDE 2 INCH CASING TO 475 FEET THEN PUMP PORTLAND CEMENT FROM TD TO SURFACE.
PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 105 SACKS OF CEMENT. WELL PLUGGED.

Remarks: CONTROL #20070018-065 GPS # LAW70 CONTRACT #09975
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: LEVI SHORT RECEIVED
TECHNICIAN KANSAS CORPORATION COMMISSION

JUL 05 2007

CONSERVATION DIVISION
WICHITA, KS

PKT